

GETZEN**517.573.5179****Estimate****Outdoor Services, Inc.**

Brooklyn, MI Tecumseh, MI
11600 Carson Hwy Tecumseh, MI 49286
matt.gosinc@gmail.com

DATE April 29, 2022
Quotation # 1106-22R
Quotation Terms 15 Days

Bill To:

Steve Cook
11300 Clinton Rd
Clinton, MI

Prepared by: Matt Getzen

End of June

Proposed Work:**Sidewalk/Patio Replacement**

Removal/disposal of existing concrete and paver blocks where new sidewalks and patio will be installed as laid out by homeowner. Prep approx 463sqft for concrete installation. Bring in crushed concrete base as needed. Grade area to a 4" depth for new concrete installation. Compact areas for a firm base. Installation of new concrete with 6 bag, 4,000psi mud with fiber mesh reinforcement for added strength and longevity. Install #4 rebar to prevent the concrete from shifting during their freeze and thaw season. Concrete to be edged and broomed finish. Return next day to remove forms, saw cut and clean.

Drain Tile

Trench for and install 4" drain tile from the two existing down spouts on the west side of the home. Trench approx 100 feet Southwest to where the drain tile will be daylighted. This should be completed at the same time as the sidewalk and patio work is completed.

Front Porch/Steps

Removal/disposal of existing concrete porch and steps. Prep approx 120sqft for concrete porch with 3 steps measuring 6 feet wide with 18" treads. Bring in crushed concrete base as needed. Grade area to a 4" depth for new concrete installation. Compact areas for a firm base. Installation of new concrete with 6 bag, 4,000psi mud with fiber mesh reinforcement for added strength and longevity. Install #4 rebar to prevent the concrete from shifting during their freeze and thaw season. Concrete to be edged and broomed finish. Return next day to saw cut and clean.

Description	AMOUNT
Patio/Sidewalks-Regular Concrete	\$4,400.00
Drain Tile	\$800.00
Front Porch/Steps - Regular Concrete	\$3,400.00
TOTAL	\$8,600.00

If you have any questions concerning this estimate please contact me. Thanks!

✓¹
2956 1/2 Due \$4300⁰⁰
1/2 Due \$4300⁰⁰

THANK YOU FOR YOUR BUSINESS!

Getzen Outdoor Services, Inc will notify MISS DIG, INC of new construction at the above address. Getzen Outdoor Services, Inc is not responsible for anything underground(not properly marked) that is hit during new construction. Getzen Outdoor Services, Inc will repair thus damages on a time and materials basis, as long as it is within the parameters of our ability.

